

① Pavement Cutting

Cutting the pavement to prepare for excavation work.



② Trial Excavation

Checking whether the work can be carried out according to the design plan.



③ Excavation

Excavating the ground to install the new water pipe.



④ Installation of New Water Pipe

Installing the new water distribution pipe.



⑤ Temporary Pavement

Temporarily paving the road after the new pipe has been installed.



⑥ Water Service Connection Replacement

Connecting each property individually to the new water pipe.



⑦ Removal of Existing Pipe

Removing the existing pipe that is no longer needed.



⑦ Removal of Existing Pipe

Removing the existing pipe that is no longer needed.



⑧ Final Pavement Restoration

Removing the temporary pavement and completing the final road surface.



⑧ Final Pavement Restoration (Completed)

The temporary pavement has been removed and the final pavement work has been completed.



Work Sequence

Work will be carried out in the order of ① through ⑧.

Before performing ② Trial Excavation, ③ Excavation, ⑥ Water Service Connection Replacement, ⑦ Removal of Existing Pipe, and ⑧ Final Pavement Restoration, pavement cutting work will be carried out first.